



419 Fifth Street, Suite 2100  
Defiance, OH 43512  
Phone 419-782-6211  
architects@beilharzinc.com

July 28, 2026

**Bryan City Schools**  
**Arts & Education Center**  
Bryan, Ohio

C4-5004

## **ADDENDUM 2**

This Addendum becomes a part of the Contract Documents and modifies them only to the extent herein set forth. Bidders shall acknowledge receipt of this Addendum on the Bid Form. Each bidder is responsible for distribution of information conveyed by this Addendum to its subbidders and suppliers.

Attachments: Sections 27 0500, 27 0526, 27 0528, 27 1116, 27 1323, 27 1413,  
27 1543, 27 4150, 27 5313, 28 1000, 28 2000, 28 3100  
Sheets P-110, P-111, P-112, P-501, P-901, P-902, P-903, EC111,  
EC112, EC501, ES501

### **ITEM NO. 1: Section 01 1000 – Summary of Work**

Add the following to paragraph 2.02.B:

4. Video monitors and wall mounts.
5. Network switches.
6. Wireless access points.
7. Telephones.

Add the following to paragraph 2.02.C:

2. Intercom system.
3. Fiber optic service entrance.

Add paragraph 2.02.D: Furnish and install pathways and cabling for the following systems, including speakers and volume controls. Audio source equipment and final connections will be furnished and installed by others.

1. Audio feeds from control booth to addition.

### **ITEM NO. 2: Section 10 2826 – Hand Dryers**

Paragraph 2.01: Add Saniflow Corp.; Machflow Plus.

### **ITEM NO. 3: Section 22 3100 – Domestic Water Softeners**

Paragraph 2.02.B: Fiberglass tanks are acceptable.

**ITEM NO. 4: Section 23 8136 – Split System Heat Pumps**

Paragraph 2.01: Add LG Electronics U.S.A., Inc..

**ITEM NO. 5: Section 23 8240 – Electric Resistance Heating Units**

Paragraph 2.01: Add TPI Corp.; Raywall.

**ITEM NO. 6: Division 27 – Communications**

Add attached Sections.

**ITEM NO. 7: Division 28 – Electronic Safety and Security**

Add attached Sections.

**ITEM NO. 8: Section 31 2000 - Earthwork**

Add the following to paragraph 3.03.F:

1. Remove soils indicated in the Geotechnical Report Test Boring Logs as Fill (except limestone), Misc. Fill, and Possible Fill from the building area; dispose of off site. Coordinate extent of removal with testing firm's Soils Engineer.
2. Existing limestone fill may remain in place, provided it is free from organic matter, non-soil materials, and other deleterious and unsuitable materials as determined by the testing firm's Soils Engineer. Prepare and proof compact subgrade as specified.

**ITEM NO. 9: Sheets P-110 through P-903 – Plumbing Drawings**

See attached plumbing drawings containing revisions required by the State of Ohio Correction Letter No. 1.

**ITEM NO. 10: Sheet E-111 – First Floor Power Plan**

Green Room 116: In northeast corner, add quad receptacle on dedicated circuit for wall mounted A/V cabinet, 48" mounting height; coordinate with Communications work.

**ITEM NO. 11: Sheets EC111, EC112, EC501, ES501 – Communications and Security**

Add attached drawings.

END OF ADDENDUM